

Ahead Beyond

Model EPD/Optima Pro Drainer[™] - Sump, Drainage









SUMP PUMPS

Model EPD/Optima

Features:

- High quality stainless steel (Note: Optima has Noryl impeller).
- Available in 1/3, 1/2, 3/4, 1, 1 1/2 HP models.
- Single and three phase models available.
- Air-filled, continuous duty rated, permanent split capacitor motors.
- Built-in thermal protection with automatic reset (single phase only)
- Built to operate whether fully or partially submerged.
- Oil lubricated double mechanical shaft seal (1/2 1 1/2HP models)
- Temperature rating to 122°F/50°C; 140°F/60°C intermittent duty.
- 20' UL/CSA approved, water resistant #16 AWG cord.
- Capacities to 88 GPM, heads to 62 feet.
- Optima and EPD slimline automatic models can operate in a 12" diameter or 8"x 8" square basin.


Applications:

- Residential
- Commercial
- Industrial
- Drainage
- Seepage
- Effluent/containment transfer
- Waste water (from trays, wet bars, washing machines)
- Empty water storage structures
- Decorative fountains
- Irrigation
- Mound systems, leach fields
- Move water/effluent to sewage systems



*Note: UL and CSA listed; Model Optima UL certified only.

SELECTION CHART



EPD/Optima



EBARA Pumps Americas Corporation 1651 Cedar Line Drive • Rock Hill, SC 29730 • (t) 803-327-5005 • (f) 803-327-5097 www.pumpsebara.com © 2018 EBARA Pumps Americas Corporation, All rights reserved.

EFHEPD1011