

# Reconstruction of Nukata Drainage Pump Station of the Musashi Canal (Outline of the Reconstruction Work and Verification of CFD Analysis)

Munetoshi FUJII\*, Fuminori ETO\*, Naoto SEGAWA\*, and Koichi YAMADA\*


## Abstract

The Nukata Drainage Pump Station is located at the end of the Musashi Canal which flows through Gyoda City and Konosu City in Saitama Prefecture. To reconstruct the deteriorated Pump Station, Pump Station No. 1 and Pump Station No. 2 were integrated, the drainage capacity was increased, and construction and civil engineering work for seismic retrofitting was done; the operation of the reconstructed pump station was officially commenced in March 2016. Based on Ebara’s technologies for pump-related facilities, we successfully completed the four-and-half-year work, including the reconstruction of mechanical and electrical facilities, the implementation of countermeasures against vortices, and civil engineering work for seismic retrofitting, while maintaining the pump station’s drainage capacity. For flow patterns in the pump sump including the upstream balancing reservoir, the results of computational fluid dynamics (CFD) analysis and the results of the conducted test were compared and verified; vortex suppression devices studied by CFD analysis are found to be efficient enough for practical use.

**Keywords:** Reconstruction, Drainage pump station, Vertical shaft mixed flow pump, Changeover, Seismic retrofitting, Pump sump, Balancing reservoir, CFD analysis, Countermeasures against vortices, Field test

## 1. Introduction

Running across Gyoda City and Konosu City in Saitama Prefecture, the Musashi Canal is a 14.5 km-long driving channel that connects the Tone River with the Arakawa River to carry purifying water and municipal water from the Tone River to the metropolitan area around Tokyo (**Figure 1**). The canal was constructed to cope with the rising demand for municipal water resulting from population increase triggered by economic growth, as well as from diversification of lifestyle, which took place in the metropolitan area from the middle 1950s to the early 1960s. In addition, the area suffered a severe water shortage due to a drought around that time. Against this backdrop, facilities associated with the Musashi Canal were built as part of the Tone Canal Project, which was planned for the purpose of stabilizing the supply of agricultural



**Fig. 1** Musashi Canal (Source: Website of Project Office for Reconstruction of Musashi Canal, Japan Water Agency)

\* Fluid Machinery & Systems Company

water provided by existing systems.

In recent years, declining soil water retention function due to further progress of urbanization, as well as unusual climatic phenomena such as local downpours, has been adding to the risk of rapidly rising river water levels and also floods in urban districts and farmlands.

Therefore, the Nukata Drainage Pump Station, one of the facilities of the Musashi Canal, plays an important role in safeguarding communities in the neighborhood of the canal from flood damage, by forcibly discharging water from the canal to the Arakawa River.

Around 50 years have passed since the construction of the facilities of the Musashi Canal, and the Project for Reconstruction of the Musashi Canal was recently implemented<sup>1)</sup> with the three main purposes of:

- (1) Recovering the water conveyance function of the canal impaired due to ground subsidence and aging of the facilities;
- (2) Ensuring and enhancing the inland water drainage function to mitigate flood damage; and
- (3) Continuously improving the water quality of the Arakawa River system.

At the Nukata Drainage Pump Station with aging facilities, Pump Stations No. 1 and No. 2 were integrated to have an increased drainage capacity of 50 m<sup>3</sup>/s (from 40 m<sup>3</sup>/s previously delivered). In addition, seismic retrofitting of buildings and substructures was carried out. Total renovation was completed in March 2016 when the facilities officially started operation.

Ebara received an order for mechanical, electrical and civil engineering work concerning pump facilities at the Pump Station No. 2 and, from July 2011 to March 2016, replaced existing pump facilities with newly manufactured ones on a step-by-step basis while maintaining a certain level of drainage capacity.

## 2. Outline of renewed pump station facilities

For major facility specifications of the renewed pump station, refer to **Table** below. **Figures 2** and **3** show plan views and a cross-sectional view of pump station layout, respectively. **Figures 4** and **5** show the appearance of the pump station.

## 3. Introduction of reconstruction work

### 3.1 Work characteristics

Main characteristics of the work are listed below:

- (1) Sequential replacement of old machines and electrical installations with new ones (**Figure 6**)

We were required to carry out the work while maintaining a certain level of drainage capacity during the reconstruction period. To this end, we removed and installed two main pumps per year (six units replaced in total), and each time carried out a commissioning check to switch from old to new equipment sequentially.

- (2) Installation of temporary pier and cofferdam in canal for drainage of pump sump section (**Figure 7**)

To install trash removal screens in the pump sump section, it was necessary to extend the existing civil engineering structures in the direction of the inflow side and construct a slab and partition walls in the canal. Therefore, we installed a temporary pier in the canal so that heavy machinery could be used on it for crane work and excavation. Moreover, we also conducted temporary water shielding by means of a cofferdam to drain the pump sump.

- (3) Reconstruction of foundation for machinery (**Figure 8**)

The pump facilities to be newly installed during the reconstruction work were expected to have different specifications from those of the old ones. For example, the new main pumps have a vertical shaft, as well as a larger bore due to increased discharge capacity. In addition, the output of the prime mover is also different from before. Consequently, we removed existing machines along with their substructures by cutting the existing concrete, while leaving the existing reinforcing bars of civil engineering structures as they are [Fig. 8 (a)]. After that, openings and substructures tailored to the renewed machines were newly constructed [Fig. 8 (b)].

- (4) Civil engineering work for seismic retrofitting (**Figure 9**)

As part of the reconstruction work, we conducted

**Table** Major facility specifications and points of renovation

| Equipment   | Pump station after renewal  | Before renewal (Station No. 2)  | Renovation points  |
|---|---|---|--|
| Main pump   | 1800 mm vertical mixed flow pump<br>7.5 m <sup>3</sup> /s × 7.7 m, 2 unit<br>1800 mm vertical mixed flow pump<br>7.5 m <sup>3</sup> /s × 8.5 m, 2 units<br>2000 mm vertical mixed flow pump<br>10 m <sup>3</sup> /s × 7.8 m, 2 units<br>Total drainage capacity: 50 m <sup>3</sup> /s   | 1500 mm horizontal mixed flow pump<br>5 m <sup>3</sup> /s, 3 units<br>1800 mm horizontal mixed flow pump<br>7.5 m <sup>3</sup> /s, 2 units<br>2100 mm horizontal mixed flow pump<br>10 m <sup>3</sup> /s, 1 unit<br>Total drainage capacity: 40 m <sup>3</sup> /s   | <ul style="list-style-type: none"> <li>• Introduction of vertical pump</li> <li>• Drainage capacity increased</li> <li>• Discharge pipe (partly), flap valves: Existing equipment used.</li> </ul>   |
| Prime mover   | Four-cycle diesel engine<br>780 kW, 2 units<br>860 kW, 2 units<br>1050 kW, 2 units  | Four-cycle diesel engine<br>550 PS (410 kW), 3 units<br>820 PS (612 kW), 2 units<br>1100 PS (821 kW), 1 unit  |  |
| Power transmission device                             | Right angle bevel gear reducer<br>(Bent pipe for discharge integrated w/ reducer)   | Planetary gear reducer  | <ul style="list-style-type: none"> <li>• Introduction of vertical pump (Bent pipe for discharge integrated w/ reducer)</li> </ul>  |
| Auxiliary machinery and equipment                     | 20 kL fuel oil tank, 3 units<br>(Existing eqpt. improved and used continuously)<br>Fuel service tank<br>1500 L, 2 units<br>1800 L, 1 unit<br>300 L, 1 unit<br>300 L oil return tank, 1 unit<br>Separate radiator system<br>For 860 kW, 4 units<br>For 1050 kW, 2 units<br>32 mm fuel transfer pump, 2 units<br>40 mm oil return pump, 1 unit<br>Air compressor, 2 units<br>Flue gas exhaust fan, 1 unit | 20 kL fuel oil tank, 3 units<br>Fuel service tank<br>1000 L, 3 units<br>490 L, 1 unit<br>330 L oil return tank, 1 unit<br>8 m <sup>3</sup> elevated water tank, 1 unit<br>100 mm cooling water pump, 4 units<br>65 mm feed water pump, 2 units<br>65 mm raw water intake pump, 1 unit<br>80 mm well water intake pump, 1 unit<br>125 mm vacuum pump, 2 units<br>40 mm fuel transfer pump, 2 units<br>25 mm oil return pump, 1 unit<br>Air compressor, 3 units (1 for emergency) | <ul style="list-style-type: none"> <li>• Cooling system changed (Separate radiator system)</li> </ul>  |
| Trash removal equipment                               | Automatic Screen<br>Rear-fall front-raking, 6 units<br>Horizontal conveyor<br>20° trough type, 1 unit<br>Incline conveyor<br>W/ Finned belt, 1 unit   | Automatic Screen<br>Trash car-type, 2 units   | <ul style="list-style-type: none"> <li>• Extension of civil engineering structures so that screens can be installed (Construction of slab and partition walls in water channel)</li> <li>• Installation of temporary pier, as well as cofferdam to drain pump sump section, in canal</li> </ul>                                      |
| Power supply facilities                               | Commercial, high incoming voltage<br>3-phase, 3-wire, 6.6 kV, 50 Hz<br>Private power generator<br>300 kVA, 1 unit<br>150 kVA, 1 unit (existing eqpt. used)  | Commercial, high incoming voltage<br>3-phase, 3-wire, 6.6 kV, 50 Hz<br>Private power generator<br>150 kVA, 1 unit   | <ul style="list-style-type: none"> <li>• Power generator room and electrical room newly provided</li> </ul>  |
| Operation & control equipment                         | 1-person operation from local operation panel<br>Central monitoring & operation: Available<br>Remote monitoring & operation: Available  | 1-person operation from local operation panel<br>Central monitoring & operation: Available<br>Remote monitoring & operation: None   | <ul style="list-style-type: none"> <li>• Installation of remote monitoring &amp; control equipment</li> </ul>  |
| Civil engineering and building<br>Other installations | Existing facilities renovated and used continuously   | —   | <ul style="list-style-type: none"> <li>• Reconstruction of foundation for renewed equipment</li> <li>• Reconstruction of pits for machines and electrical installations</li> <li>• Seismic retrofitting of civil engineering structures and building</li> <li>• Cranes:<br/>Existing eqpt. improved and used continuously</li> </ul> |

Note: For reference, specifications of the pump station before renewal (Station No. 2) are also shown in the above table.

civil engineering work for seismic retrofitting, such as installation of shear reinforcement bars and reinforcement steel sheets in/on the slab, and partition walls of the pump sump.

### 3.2 Construction challenges

The challenge level of the work is evaluated as “difficult”

(rated V of VI). During the long work period, we were required to steadily and reliably proceed with the processes one by one while maintaining a certain level of drainage capacity, which was a big challenge to us.

The parties involved always tried to have an overall view of the work, with particular efforts focused on the




Fig. 2 (a) Plan view of pump station layout (before renewal)




Fig. 2 (b) Plan view of pump station layout (after renewal)




Fig. 3 Cross section of pump station (after renewal)



Fig. 4 Appearance of pump station (exterior)




Temporary pier installed in canal



Excavation work at pump sump section



Fig. 5 Appearance of pump station (interior)



Cofferdam  
Existing civil engineering structure  
Naturally flowing water channel  
Extension of partition wall  
Construction of slab

Fig. 7 Installation of temporary pier and cofferdam, and construction work in canal




Fig. 6 Scope of work (by phase)

matters listed below, and implemented elaborate construction PDCA cycles, as part of which periodic project meetings were held in and outside the company. By doing this, we realized the assurance and improvement of work quality and safety while adhering to the prescribed work schedule, and successfully completed the work.



(a) Removal of existing equipment



(b) Construction of foundation for renewed equipment

**Fig. 8** Reconstruction of machine foundation

(1) Confirmation of construction conditions by means of careful field investigation  
 Verification of existing civil engineering structures, check for interference of machines and piping, etc.

(2) Preparation of efficient renewal schedule  
 Rational configuration of machine/electric equipment changeover sequence and relocation method  
 Improvement of workability by devising suitable installation and suspension jigs\*

\* While an existing pump station building and cranes were to be used continuously, previously used horizontal-type main pumps were to be replaced by vertical-type ones, resulting in an increase in weight and thus making it impossible to lift by crane a full set of assembled pump components at one time. Also, the lifting margin was limited due to the engine exhaust duct layout. Considering these constraints, we produced special jigs (**Figure 10**).



Installation of shear reinforcement bars



Installation of reinforcement steel sheets

**Fig. 9** Civil engineering work for seismic retrofitting (Pump sump section)

- (3) Thorough coordination of work schedule  
 Progress management always keeping an eye on the overall schedule including other work items (architectural equipment, seismic retrofitting of building, etc.).
- (4) Assurance and improvement of work safety  
 Prevention of falls into the fast-flowing canal, etc.

### 3.3 Design measures

On the basis of our accumulated expertise in pump-related facilities, we devised various measures to improve reliability and maintainability of the equipment and to extend its service life, while giving consideration to the characteristics of the worksite. For instance, the following measures were taken:

- (1) Improvement of pump efficiency to save fuel cost
- (2) Countermeasures against vortices in the pump sump based on CFD analysis
- (3) Improvement of reliability and maintainability



**Fig. 10** Carrying-in and emplacement of main pump using installation and suspension jigs

- The range of operational water levels for inside water (Musashi Canal) is short.
- A control logic was developed to flexibly regulate flow rate by changing rotation speed and discharge valve opening in accordance with inflow volume.
- Improved reliability of the cooling system is demanded.
- To cope with unexpected failure of separately installed radiator fans, a function of automatic switching to backup fans was added.
- Space in the pump station building is confined.
- To maximally ensure the smooth flow of workers and materials, as well as sufficient maintenance space, inventive measures were devised for the layout of exhaust ducts and supports, as well as for the lid of the opening in the vacant space (securing of load capacity to bear the weight of temporarily placed

equipment; elimination of unevenness).


As the pump renewal work was expected to increase discharge capacity, we deemed the countermeasures against vortices generated in the pump sump (**Figure 11**) as the most important theme to be addressed. So, we provided devices to cope with these pump sump vortices with use of CFD analysis, as we presented the outline in the previous report<sup>2)</sup>. This time we report on the results of a verification of CFD analysis conducted at the time of the field commissioning.

#### 4. Application of CFD analysis

##### 4.1 Outline

The pump sump of the Nukata Drainage Pump Station is arranged to receive water that comes from the upstream balancing reservoir and makes a right-angled turn when flowing into the sump. Also, some pumps (No. 3 and 4) were scheduled to be renewed to have larger drainage capacity while partition walls dividing the subsections of the pump sump were to be extended, leading to a greater likelihood of drift flows in the pump sump. Consequently, it was expected that there would be an increased risk of emergence of harmful vortices (i.e. air-entraining vortices and submerged vortices) that could affect the operation of pumps.

As reported in the previous report<sup>2)</sup>, we then analyzed the flow patterns in the pump sump along with the upstream balancing reservoir and carried out



**Fig. 11** Configuration of vortex suppression devices

a model testing, in order to study the configuration of anti-vortex devices. Fig. 11 shows the configuration of vortex suppression devices optimized using CFD analysis. On top of that, this time we proved the effectiveness of the vortex suppression devices configured with the help of CFD analysis, based on the data obtained through the test operation of real equipment during the comprehensive commissioning conducted prior to the completion of the renewed Nukata Drainage Pump Station. We also checked the validity of the CFD analysis we conducted.

**4.2 Field test**

The test was conducted by operating the No. 4 pump only (with 1800 mm bore and rated discharge capacity of 7.5 m<sup>3</sup>/s), which was expected to have the greatest drift of flow coming from the balancing reservoir.

**Figure 12** shows the situation of inflow and outflow of water from the balancing reservoir at the time of the field test. The pump’s discharge capacity was calculated based on the pump performance curve obtained in a factory performance test, the water level conditions at the time of the field test, and piping and valve-related losses. As the discharge capacity of the pump exceeded the rated value, the test was conducted under conditions where vortices were likely to occur in the pump sump.

(1) Measurement of flow velocity in pump sump

A pair of three-dimensional electromagnetic


velocity meters were used to measure the flow velocity in the pump sump. One velocity meter was installed in each of the left and right water channels divided by a center pier, as shown in Fig. 12.

(2) Observation of water surface flow adjacent to pump suction pipe


In general, the pump sump of a rainwater drainage pump station is designed as a closed conduit, making it difficult to perform direct visual observation of vortices generated while the pump is operating. In this test, we used an industrial endoscope inserted from the pump base to capture and observe the water surface flow adjacent to the pump suction pipe.

**4.3 Test results**

**Figure 13** shows the time variations of the flow velocity in the pump sump (stream-wise component in the sump) when the No. 4 pump is independently running. Data revealed that the flow velocity tended to be higher in the left channel than in the right when the pump was viewed from the upstream side. The average flow velocity within the time range indicated in Fig. 13 was 1.89 m/s for the left channel, and 1.47 m/s for the right channel. Then, these averages were deemed as representative flow velocity values and converted to flow rate, on the assumption that no water-level difference occurs between the left and right



**Fig. 12** Field test conditions



**Fig. 13** Flow velocity in No.4 pump sump


channels; as a result, the flow in the left channel accounted for 56% of the total, and that in the right channel 44%.

**Figure 14** shows the water surface flow around the pump suction pipe, which was observed by means of an industrial endoscope while the pump was in operation. We found no swirling flow during the test run, and confirmed that no air-entraining vortices would be generated.


**4.4 Reproduction simulation of actual equipment test by CFD analysis**

In the previous report<sup>2)</sup>, we divided the balancing reservoir from the pump sump and conducted detailed analysis of vortical flows in the pump sump by using the results of flow analysis on the balancing reservoir as inflow conditions. In this way, we could verify the effects of various configurations of vortex suppression devices within the limited time for study at that time. Meanwhile, CFD analyses classified as large-scale analysis have also become feasible these days, owing to the improvement of computer performance in recent years. So, this time we conducted CFD analysis on the balancing reservoir and pump sump in an integrated manner, compared the results with the measurements obtained from the actual equipment, and verified the accuracy of the analysis.


We conducted a steady state analysis using the Reynolds-averaged Navier-Stokes (RANS) model, not taking water surface fluctuations into account. **Figures 15** and **16** respectively show a vector diagram of flow velocity in the balancing reservoir and an enlarged view of inflow into the pump sump. The proportion of the flow in both the channels was 58% for the left channel and 42% for the right channel, fairly consistent with the results of the field test.



**Fig. 14** Water surface flow adjacent to pump suction pipe



**Fig. 15** CFD analysis results of pump sump along with balancing reservoir



**Fig. 16** Inflow into No.4 pump sump

**Figure 17** presents the distribution of the velocity vectors at the water surface, as well as the vortex core lines, in the pump sump. Although several vortex cores are observed, they are not harmful, showing that the vortex suppression devices are effective. Flow patterns at the water surface are also highly consistent with the observation of the actual equipment (**Fig. 14**); this means that the flow conditions during the actual equipment test were successfully reproduced with good accuracy, by means of the large scale CFD analysis on the balancing reservoir and pump sump.

As described above, we confirmed that the study of configuration of vortex suppression devices using CFD




Fig. 17 CFD analysis results of pump sump

analysis is sufficiently applicable for practical use, which was proved as a result of verification by comparison with actual equipment test results.

## 5. Conclusion

The reconstruction work was rated as “difficult” in terms of challenge level, and involved (i) the sequential replacement of equipment in parallel with the retention of a certain level of drainage capability; (ii) provision of vortex suppression measures; (iii) construction of temporary pier and cofferdam in the canal; (iv) civil engineering work for seismic retrofitting; and so on. We were required to adhere to the long work schedule, and had tasks of ensuring and improving work quality and

safety. All persons involved are proud that they successfully completed the work by dedicating a long list of creative efforts to tackling design and construction issues on the basis of a good understanding of the characteristics of the worksite.

As the contractor of the work, we received an award under the name of the Chairman of Tone Canal Management and Construction Office Safety Council, for our excellence in safety management in FY2015 (annual award for achieving zero accidents).

Finally, we should mention that we received the guidance and cooperation from many people in and outside our company, including those from the Japan Water Agency, with regard to the reconstruction work. We would like to sincerely express our gratitude to the parties concerned.

## References

- 1) Rebirth of Musashi Canal: Musashi Canal Reconstruction Project. Project Office for Reconstruction of Musashi Canal, Tone Canal Management and Construction Office, Japan Water Agency. 2012.
- 2) Fuminori ETO, Lingjia ZHAO, and Norihiko OWADA. “Applying of CFD Analysis to Countermeasures against Undesirable Vortices in a Pump Sump at the Reconstruction of Nukata Drainage Pump Station.” *Ebara Engineering Review*, No. 240, p. 22-26. July 2013.